

RESEARCH

Open Access



Filter cake extract from the beet sugar industry as an economic growth medium for the production of *Spirulina platensis* as a microbial cell factory for protein

Sara Saad¹, Mervat Hosny Hussien¹, Ghada Samir Abou-ElWafa¹, Heshmat Soliman Aldesuquy¹ and Eladl Eltanahy^{1*}

Abstract

Background Beet filter cake (BFC) is a by-product of sugar beet processing, which is difficult to dispose of and involves severe environmental concerns. *Spirulina platensis* is a microalga with a high protein content essential for human and animal nutrition. The present study aimed to utilize the beet filter cake extract (BFCE) to produce *Spirulina platensis* commercially. However, the cultivation of *S. platensis* on BFCE to produce economically single-cell protein has not been reported previously.

Results The batch experiment revealed the maximum dry weight at Zarrouk's medium (0.4 g/L) followed by 0.34 g/L in the treatment of 75% BFCE. The highest protein content was 50% in Zarrouk's medium, followed by 46.5% in 25% BFCE. However, adding a higher concentration of 100% BFCE led to a protein content of 31.1%. In the adaption experiment, *S. platensis* showed an increase in dry cell weight and protein content from 25 to 75% BFCE (0.69 g/L to 1.12 g/L and 47.0% to 52.54%, respectively) with an insignificant variation compared to Zarrouk's medium ($p \leq 0.05$), indicating that *S. platensis* can be economically produced when cultivated on 75% BFCE. The predicated parameters from response surface methodology were NaNO_3 (2.5 g/L), NaHCO_3 (0.67 g/L), BFCE (33%) and $\text{pH} = 8$, which resulted in biomass yield and protein content (0.56 g/L and 52.5%, respectively) closer to that achieved using the standard Zarrouk's medium (0.6 g/L and 55.11%). Moreover, the total essential amino acid content was slightly higher in the optimized medium (38.73%) than SZM (36.98%).

Conclusions Therefore, BFCE supplemented medium could be used as a novel low-cost alternative growth medium for producing a single-cell protein with acceptable quantity and quality compared to the standard Zarrouk's medium.

Keywords Sugar beet, Beet filter cake, Single cell protein, *Spirulina platensis*


*Correspondence:

Eladl Eltanahy
eladl@mans.edu.eg

Full list of author information is available at the end of the article



© The Author(s) 2023. **Open Access** This article is licensed under a Creative Commons Attribution 4.0 International License, which permits use, sharing, adaptation, distribution and reproduction in any medium or format, as long as you give appropriate credit to the original author(s) and the source, provide a link to the Creative Commons licence, and indicate if changes were made. The images or other third party material in this article are included in the article's Creative Commons licence, unless indicated otherwise in a credit line to the material. If material is not included in the article's Creative Commons licence and your intended use is not permitted by statutory regulation or exceeds the permitted use, you will need to obtain permission directly from the copyright holder. To view a copy of this licence, visit <http://creativecommons.org/licenses/by/4.0/>. The Creative Commons Public Domain Dedication waiver (<http://creativecommons.org/publicdomain/zero/1.0/>) applies to the data made available in this article, unless otherwise stated in a credit line to the data.



Background

Sugar cane and sugar beet account for most of the sugar produced in Egypt and worldwide. Sugar beet was grown on 207,527 hectares in 2019 and is Egypt's largest source of sugar production. The sugar industry starts with sucrose extraction from sugar beet using hot water resulting in raw juice, which is then purified, filtered, and concentrated by cyclic rinsing and evaporation. During the clarification of beet juice, milk of lime and sulfur dioxide are added to neutralize the juice's acidity and precipitate the non-sugar components. The residue is settled in a clarifier, and the settled sludge is filtered using a rotary vacuum filter [1].

Solid waste is produced as a by-product of the clarification of juice before its concentration and crystallization, called beet filter cake (BFC), also known as press mud, which is relatively rich in organic matter and some minerals causing a disposal problem [2]. The sugar factories dispose of these wastes in the open landscapes polluting the natural environment of that area. Therefore, recycling this waste is essential to reduce environmental pollution significantly and improve sustainability [1, 3]. Many scholars have studied the effect of BFC on biodiesel [4], crop productivity, soil fertility, and the possibility of its utilization as an organic fertilizer, but it is limited due to transport costs and soil acidity [5, 6].

Spirulina platensis is an economically crucial filamentous cyanobacterium naturally grown in alkaline water and warm regions and commercially produced for human and animal consumption [7, 8]. The *Spirulina*

deserves special attention as a microbial cell factory for edible protein production (70% of dry biomass), essential amino acids, fats, and carbohydrates [9]. Moreover, bioactive compounds such as phycocyanin, chlorophylls and phenolic compounds benefit human health [10, 11]. *S. platensis* commercial cultivation on the standard Zarrouk's medium as a selective medium that minimizes contamination requires excessive nutrients, especially NaHCO_3 , for both carbon source and pH control. The production cost of the growth medium is relatively high because NaHCO_3 concentration is 16.8 kg/m^3 , which is a limiting factor for large-scale cultivation and economic feasibility [12].

Single-cell protein (SCP) is a dried biomass of high protein content that can be used as an alternative protein in animal feed or human nutrient supplements. Different microorganisms like yeast, bacteria and cyanobacteria can produce SCP, such as *S. platensis* [13]. The commercial trend for SCP production depends on using wastes from agriculture and food residues, which are cheap, non-toxic, renewable substrates, resulting in biomass of high protein content and waste management [14]. Utilizing the BFC in cultivating *S. platensis* as a microbial cell factory for single-cell protein has not been reported in the literature. Therefore, this study aims to formulate a new cost-effective medium using BFC supplementation which can minimize environmental pollution and production costs as possible while maintaining high biomass and protein content by optimization of the different growth variables incorporated in the medium for

maximum biomass and protein yield in both photobioreactors and outdoor open ponds.

Results and discussion

BFCE analysis

Analyzing the BFCE components is critical because detecting toxic heavy elements or other pollutants will result in harmful, unaccepted *S. platensis* alga products in food or feed applications. Since this waste is from one of the clean food industries' wastes, the result of the analysis of the various elements in the extract using inductively coupled plasma mass spectrometry (ICP-MS) was as expected and at a minimum level; moreover, mercury, cadmium, and copper were not detected. On the other hand, the Ca⁺⁺ and Na⁺ were at 565 ppm and 391 ppm, respectively, which are acceptable values. Also, ammonia, nitrate, and phosphate were 2.05 ppm, 4.84 ppm and 50.1 ppm, respectively (Table 1).

Batch culture experiment

Photosynthetic activity

In this experiment, the photosynthetic activity of *S. platensis* grown in both standard zarrouk's medium (SZM) and BFCE was measured every day to assess the impact of BFCE on photosynthesis performance. Richmond et al. [15] reported that the Fv/Fm values of non-stressed green microalgae range between 0.7 and 0.8, depending on environmental and culturing conditions. However, the values of the cyanobacterial cell range between 0.4 and 0.6 as phycobiliproteins interfere with the fluorescence

signal of the chlorophylls inside the cell [16, 17]. In this experiment, Fv/Fm values of all treatments were within the acceptable ranges compared to the SZM, but they showed a decrease to a range below 0.50 in both treatments 75% and 100% on the 2nd day of the experiment due to the stress induced by high concentrations of BFCE at the beginning of the experiment. Later, the alga adapted to this change in the medium nutrient content for 75% and 100% treatments. At the end of the experiment on the 7th day, the lowest activity was in the SZM, and this may be due to low nutrient availability caused by *S. platensis* utilization or due to a self-shading effect caused at the end of log growth phase, which effect on photosynthetic potential [18, 19], while 75% and 100% were the highest values, as shown in Fig. 1 and Additional file 1: Fig. S1.

Numerous studies have shown that Fv/Fm values obviously change by stress conditions during growth, such as high light intensity, nutrient deficiency, oxygen, radiation, and excess heavy or toxic elements [20–23].

Evaluation of growth by optical density

S. platensis growth rate increases in all concentrations until the fifth day, but the growth decreases in the 75% BFCE on the sixth day and then increases again. Similarly, the growth declined in the 100% BFCE (Fig. 2). The high BFCE concentration resulted in lower biomass accumulation due to insufficient nutrients. Furthermore, the growth of 50% BFCE treatment (0.3–1.24) was closer to the SZM (0.2–1.53) but less than it, with an unclear sudden decline in the 6th day followed by growth recovery by the 7th day, which may be due to the non-uniform culture density causing *S. platensis* clumps.

Estimation of dry-weight biomass

As shown in Fig. 3, the highest dry weight determined of *S. platensis* was in SZM (0.41 ± 0.04 g/L), followed by 75% BFCE (0.34 ± 0.03 g/L), while the minimum dry biomass was at 50% BFCE (0.25 ± 0.007 g/L). The variation in dry cell weight was significantly decreased (p ≤ 0.05) in different concentrations of BFCE except for 75%, which gave a non-significant decrease compared to the SZM.

Chlorophyll-a, b and carotenoids determination

The chlorophyll-a concentration is directly related to biomass concentration and protein content. The maximum chlorophyll-a concentration (19.284 ± 3.6 mg/g) was obtained in 50% BFCE, followed by the SZM (12.0 ± 0.6 mg/g), while the concentration of chlorophyll-b in SZM and 50% BFCE was almost similar as shown in Fig. 4. All pigment concentrations declined when the BFCE concentration was increased to 100%. Further addition of BFCE up to 50% resulted in a significant

Table 1 Inductively coupled plasma mass spectrometry analysis of elements NH₃, NO₃, and P in BFCE

Element	Concentration (ppm)	Element	Concentration (ppm)
Al	271.9	Fe	22.848
Se	0.258	Ga	0.51
V	0.482	In	5.766
Bi	0.916	K	34.874
Hg	ND	Li	0.275
Ag	0.749	Mg	55.975
B	0.97	Mn	0.987
Ba	0.285	Ni	2.816
Ca	565.7	Pb	2.3
Cd	ND	Sr	0.879
Co	0.149	Zn	1.414
Cr	13.614	As	0.194
Cu	ND	Na	391.06
NH ₃	2.05	NO ₃	4.84
P	50.1		

ND none detected elements




Fig. 1 Optimal quantum yield (Fv/Fm) in *S. platensis* ± SE cultivated in the SZM and BFCE treatments




Fig. 2 Optical density of *S. platensis* ± SE cultivated in the SZM and BFCE treatments

increase in carotenoids content (4.5 ± 1.19 mg/g) compared to SZM (2.24 ± 0.18 mg/g), but other concentrations showed non-significant differences with SZM.

Estimation of protein

The standard nutritional profile of *S. platensis* is proteins (50–70%), carbohydrates (15–25%), lipids (6–8%) and

minerals (7–13%). These significant components' percentages alter with the cultivation conditions of the alga [12]. In agreeing with these ranges, the highest protein concentration in this study was $50.98 \pm 8.9\%$ in SZM, followed by 25% ($46.56 \pm 1.4\%$), then 50% ($39.11 \pm 0.36\%$). In contrast, at 100% of BFCE, the biomass contained in lower protein content equals $31.1 \pm 2.4\%$ (Fig. 5).




Fig. 3 Dry weight of *S. platensis* ± SE cultivated in the SZM and BFCE treatments




Fig. 4 Photosynthetic pigments in *S. platensis* ± SE cultivated in the SZM and BFCE treatments

In a relevant study [24], the protein content in *S. platensis* biomass cultivated in raw piggery effluents medium was 45.31%, while supplementation with ferrous sulfate caused an increase in the protein content up to 55.15%. Similarly, direct cultivation of *S. platensis* at different

concentrations of BFCE had a significant negative impact on the protein content at $p \leq 0.05$ by increasing the BFCE concentrations. Because the BFCE is limited in nutrient content compared to the standard growth medium, and as a result, these conditions cause a nutrient deficiency,




Fig. 5 Protein content in *S. platensis* ± SE cultivated in the SZM and BFCE treatments

especially nitrogen concentration, which affects the protein content. In agreement, Uslu et al. [25] concluded that the lack of NaNO₃ limited protein synthesis, which resulted in a protein productivity decline.

Total carbohydrate estimation

The carbohydrate content in *S. platensis* culture, which was cultivated in this experiment, showed a generally increasing trend, as shown in Fig. 6; all treatments of




Fig. 6 Carbohydrates content in *S. platensis* ± SE cultivated in the SZM and BFCE treatments

75%, 50%, 25%, and 100% BFCE produced higher carbohydrate contents ($15.07 \pm 0.5\%$, $11 \pm 0.5\%$, $10.9 \pm 0.12\%$ and $11.0 \pm 0.1\%$, respectively) compared to SZM which had only $7.28 \pm 0.54\%$ of carbohydrates. This trend in the induction of carbohydrates content agreed with the results of growing different microalgae such as *Chlorella vulgaris*, *Phaeodactylum tricornutum*, and *Micractinium pusillum* in other mixotrophic growth conditions [26–29].

The carbohydrate content was enhanced by increasing the BFCE concentrations to 75% ($15.07 \pm 0.58\%$), which significantly differs from SZM ($7.28 \pm 0.5\%$). In comparison, the pure BFCE 100% led to decreased carbohydrate content. In SZM, *S. platensis* grows autotrophically using only carbon dioxide and sodium bicarbonates as the sole carbon source for carbohydrate accumulation. However, in SZM supplemented with BFCE with different ratios, *S. platensis* grew mixotrophically, simultaneously accumulating more carbohydrates from other carbon sources in BFCE.

Total lipid estimation

The lipid content represented in Fig. 7 showed that the SZM had the highest value up to $8.14 \pm 0.26\%$, while 25% of BFCE resulted in only $6.56 \pm 0.07\%$ lipids. In the same reversal relationship between BFCE and lipids content, the 50%, 75% and 100% BFCE concentrations produced $7.62 \pm 0.8\%$, $5.13 \pm 0.1\%$, and $4.26 \pm 0.18\%$, respectively.

In general, *S. platensis* lipid contents showed relatively low proportions; therefore, higher BFCE concentrations

showed no remarkably significant impact on lipid accumulation in the lyophilized biomass. These results were lower than that obtained by Chang Y, et al. [30] (17.2–19.8%), they cultivated *S. platensis* on synthetic human urine for biomass production and nutrient removal. Also, Li et al. [31] obtained the same results when studying nitrogen limitation's effect on *S. platensis* performance cultivated mixotrophically.

Incremental waste acclimatization experiment

Photosynthetic activity

The functional consequences of changes in the maximum photochemical efficiency of photosystem II inferred by the Fv/Fm values of dark-adapted cultures and a decline in the value of this parameter are thought to be a sign of environmental stress or nutritional depletions [32]. For instance, in *S. platensis*, the electron transport chain in PS II was reported to be damaged by the effect of increasing salinity [33]. At the start of the experiment, in both treatments, the Fv/Fm was 0.5, then decreased to 0.4 during all cultivation periods. In addition, the Fv/Fm values of BFCE from 25 to 75% were consistent with the values of SZM, confirming that *S. platensis* can adapt to grow up to 75% BFCE. On the other hand, it decreased dramatically from 0.5 to approximately 0.1 at 100% BFCE. Increasing the BFCE to 100% revealed stress in these culturing conditions causing a decline in the photosynthetic efficiency and adaption potential, as illustrated in Fig. 8. Moreover, this is due to the BFCE containing restricted amounts of nutrients, especially nitrogen and phosphate,




Fig. 7 Lipid content in *S. platensis* \pm SE cultivated in the SZM and BFCE treatments




Fig. 8 Optimal quantum yield (Fv/Fm) in *S. platensis* ± SE cultivated in the SZM and BFCE treatments

compared to the standard medium for *S. platensis* growth. Consistent with Liu et al. [34], they observed a reduction in Fv/Fm values when microalga *Phaeodactylum tricornutum* was grown in a mixotrophic mode of nutrition. Also, Tang et al. [35] reported that the Fv/Fm of *Scytonema javanicum* during their experiments was significantly decreased by salinity stress during growth.

The high concentrations of BFCE decreased the *S. platensis* growth rate, photosynthetic pigment, protein, carbohydrates, and lipid contents. Based on the naked eye optical observation, the culture colour turned from blue-green to yellow-green by the last run when BFCE totally replaced SZM. This could be due to the insufficient

nitrogen content in the cultivation medium, which makes *S. platensis* utilize the pigments as a nitrogen storage material for alternative protein synthesis. These results are harmonious with many studies [36, 37].

Evaluation of growth optical density

The behaviour of *S. platensis* in SZM and BFCE-supplemented media was an almost similar trend (Fig. 9), indicating that *S. platensis* had adapted to grow on specific concentrations of BFCE up to 75%. On the other hand, there was a significant decrease at 100% BFCE (0.31 ± 0.02) as shown in Additional file 1: Fig. S2, which could be attributed to the limitation effect on the




Fig. 9 Optical density of *S. platensis* ± SE cultivated in the SZM and BFCE treatments

photosynthetic rate of *S. platensis* showing that combining nutrients from SZM and BFCE is better for *S. platensis* biomass production on a large scale than BFCE alone, which is limited in its nutritional components.

Estimation of dry-weight biomass

As shown in Fig. 10, The cell dry weight of *S. platensis* increased with the gradual rising of BFCE up to 75% (1.122 ± 0.063 g/L) with a non-significant difference. Excessive BFCE concentrations, up to 100%, had a remarkable negative impact on the cell dry weight of *S. platensis* (0.49 ± 0.034 g/L), revealing that *S. platensis* dry weight increasing trend is similar to the optical density, up to 75% BFCE.

Chlorophyll-a, b determination

The chlorophyll content of *S. platensis* biomass depends on medium composition, particularly the kind and amount of nitrogen [38, 39]. The chlorophyll-a increased in *S. platensis* cultivated in SZM during the entire experiment period. However, it raised to (5.6 ± 0.3 mg/g) when the BFCE concentration was increased to 50%, but it dropped again when the concentration was raised to 100% (3.5 ± 0.4 mg/g). Moreover, the chlorophyll-b increased when using 25% and 50% BFCE over the SZM, then decreased again in 100% BFCE concentration

(Fig. 11). In this design the carotenoids not detected in BFCE expect at 100% BFCE concentration (0.57 mg/g), while in SZM the concentration increased from 0.37 to 1.70 mg/g during cultivation period. The feasibility of using low BFCE concentrations along with SZM in *S. platensis* cultivation was significant because the growth, photosynthetic activity, dry weight, and photosynthetic pigment were not affected. While at higher concentrations of BFCE, the cell growth and photosynthetic activity were significantly decreased, consequently causing a decrease in chlorophyll contents. Furthermore, similar results were recorded and concluded that pigment content in *S. platensis* was lower in mixotrophic than autotrophic conditions [31].

Estimation of protein

According to the data presented in Fig. 12, the protein content increased from $47.18 \pm 0.9\%$ to $52.54 \pm 1.7\%$ in treatments from 25 to 75% BFCE with minor variation compared to the SZM ($p \leq 0.05$). However, a considerable reduction in protein content was observed at 100% BFCE concentration. At the same time, the SZM varied from 42.84% protein in the 1st week of the experiment to 60.66%, which was the maximum peak value of protein production, in the 2nd week.




Fig. 10 Dry weight of *S. platensis* ± SE cultivated in the SZM and BFCE treatments




Fig. 11 Photosynthetic pigments in *S. platensis* ± SE cultivated in the SZM and BFCE treatments. **A:** Chlorophyll-a in mg/g dry weight and **B** Chlorophyll-b in mg/g dry weight

It is known that nitrogen is one of the limiting factors that affect the growth and chemical composition of cyanobacteria [40] and the accumulation of nitrogen-rich biomolecules such as protein in microalgal biomass

is directly related to nitrogen availability in the nutrient medium [41].

As mentioned, BFCE contains less nitrogen than the SZM used for *S. platensis*. Gradually supplying the SZM




Fig. 12 Protein content in *S. platensis* \pm SE cultivated in the SZM and BFCE treatments

with BFCE led to an increase in protein content. However, at 100% BFCE, a significant protein content reduction was noticed at only 21.16% compared to SZM, which produced 47.80% protein. These results were consistent with Piorreck et al. [42], they observed that the increase in the nitrogen level supports an increase in biomass, protein content, and chlorophyll. In agreement with these results, the *Spirulina maxima* was grown on fermented cattle, and poultry manure with high nitrogen showed a 60.1% and 71.8% protein content, respectively [43]. Considering the criteria of economic feasibility studies, it is clear that the optimum use of BFCE as additives to the growth medium is 75% because the decrease in protein production is not significantly different from the SZM.

Total carbohydrates determination

Carbohydrates content increased from $6.65 \pm 0.3\%$ to $14.39 \pm 0.09\%$ in treatments 25% to 75% BFCE with an insignificant difference ($p \leq 0.05$) compared to SZM (Fig. 13). Moreover, it revealed a considerable reduction in the carbohydrates content at 100% BFCE concentration equal to $7.58 \pm 0.5\%$, which may be attributed to the reduction in growth rate due to the low availability of nutrients with the increase in the BFCE concentration in the culture medium.

The enhanced carbohydrates content in *S. platensis* may be attributed to the utilization of organic carbon in

the BFCE as a carbon source in addition to photosynthesis. Likewise, a similar study reported an improving in carbohydrate content in *S. platensis* growing on tofu wastewater enriched with various organic carbon [44].

Total lipid determination

The lipid content increased from $4.92 \pm 0.07\%$ to $6.55 \pm 0.13\%$ in treatments 25% and 75% of BFCE, which was almost similar to that of SZM ($3.85 \pm 0.38\%$ to $7.71 \pm 0.5\%$). In contrast, 100% BFCE resulted in only $2.66 \pm 0.4\%$. The lipid content of the biomass was not significantly affected by the different concentrations of BFCE (Fig. 14). The difference compared to the SZM was insignificant at $p\text{-value} \leq 0.05$, in general.

In another study investigating the effect of nitrogen concentration as NaNO_3 on the lipid accumulation in *S. platensis*, the maximum lipid production was 4.7% at 15 °C in a nitrogen-free medium. In contrast, the best growth and lipid production was at 35 °C and 1.25 g/L of sodium nitrate [45].

In general, a slight difference between all SZM during the four weeks of the experiments is owing to the variation in the inoculum dry weight (g/L) which coincide with Pelizer et al. [46], they stated that the best inoculum age was six days with 50 mg/L of concentration and changing this ratio will impact on the final dry weight and biochemical composition of the biomass.




Fig. 13 Carbohydrates content in *S. platensis* ± SE cultivated in the SZM and BFCE treatments




Fig. 14 Lipid content in *S. platensis* ± SE cultivated in the SZM and BFCE treatments

Optimization of growth parameters using central composite design (CCD)

Factors such as NaNO₃, NaHCO₃, BFCE and PH were predicted to affect the *S. platensis* growth and protein yield. Moreover, NaNO₃ and NaHCO₃ are the main costly elements in the SZM and highly considered in the economic feasibility of large-scale production of *S. platensis* while BFCE is a massive sugar industry waste with non-significant application and cheap prices. On the other hand, it is a source of carbonates and still contains impurities from the sugar industry [47] which considered as a valuable nutrient for *S. platensis*. A CCD matrix was performed to detect the appropriate NaNO₃, NaHCO₃, BFCE and PH controlling the maximum biomass and protein yield. Biomass growth is expressed as dry weight (g/L) and protein yield (%). The optical density and photosynthetic activity (Fv/Fm) of *S. platensis* cultivated using CCD matrix are shown in Additional file 1: Table S1. The matrix and responses of the design are shown in Table 2 and Additional file 1: Fig. S3. The maximum protein was 54.40%, and biomass dry weight was 0.74 g/L in runs number 2 and 15, respectively. In run number 2 when the NaHCO₃ was reduced to 25% of the initial content (4.2 g/L), the protein content and dry biomass were nearly the same as SZM. This contradicts the conclusion that appeared with Raouf et al. [48] reported that the reduction in the bicarbonate concentration to 4 g/L in the formulated medium led to a significant decrease in biomass, chlorophyll and protein content. In run number 15, when the NaNO₃ reduced to 1.075 g/L led to a decrease in protein content compared to the SZM and the response surface quadratic model for biomass yield and protein concentration are tabulated in Table 3.

Analysis of the main effect, quadratic effect and interaction between factors with *p*-value < 0.05 was considered significant, as shown in Table 3.

Second-order polynomial models that predict the biomass dry weight and protein yield as a function of the experimental variable are shown in Eqs. (1 and 2).

For biomass dry weight:

$$\begin{aligned}
 Y_1 = & 0.543 + 0.0053 * A + 0.0217 * B + 0.0445 * C + 0.0328 * D \\
 & + 0.0051 * A^2 + 0.0137 * B^2 + 0.0112 * C^2 + 0.0229 * D^2 - 0.0084 * AB \\
 & - 0.0515 * AC - 0.0051 * AD - 0.0285 * BC + 0.0015 * BD + 0.0401 * CD
 \end{aligned}
 \tag{1}$$

For % protein:

$$\begin{aligned}
 Y_2 = & 44.25 + 1.344 * A + 2.34 * B - 1.198 * C - 1.35 * D + 0.389 * A^2 \\
 & - 1.89 * B^2 + 0.688 * C^2 - 1.147 * D^2 - 2.51 * AB + 2.48 * AC - 1.71 * AD \\
 & + 1.23 * BC + 0.0015 * BD - 0.65 * CD
 \end{aligned}
 \tag{2}$$

From the ANOVA analysis (Table 3), The model is significant for biomass yield and protein concentration, with *p*-value of 0.0074 and 0.04, respectively. The different independent factors with a *p*-value less than 0.05 indicate that they are significant model terms. Regarding biomass yield, the BFCE (C) and pH (D) significantly affected the biomass yield with *p*-values of 0.004 and 0.030, respectively. The interaction of BFCE with pH (CD) also significantly affected the biomass yield with *p*-values of 0.030.

The interaction between the tested variables on the dry biomass was created by response surface plots (Fig. 15). The deep red colour indicates the direction of the optimum condition for the response. Regarding the interaction between NaNO₃ (A) and NaHCO₃ (B), the later optimum concentration was 4.2–16.8 g/L. While in NaNO₃ (A) and waste (C), the optimum waste concentration was 55–75%. At the same time, NaNO₃ range was 0.6–1.47 g/L in both interactions. However, in its interaction with waste or pH, its optimum range was 0.6–1.93 g/L, and the optimum ranges for waste and pH were 55–75% and 9.2–11, respectively. Finally, in the interaction between NaHCO₃ (B) and waste, the optimum range for waste was 65–75%. While in NaHCO₃ (B) and pH (D), the optimum pH was 9.8–11. Moreover, a NaHCO₃ concentration of 0–16.8 g/L was the optimum concentration in the interaction with waste and pH.

Regarding the protein, as shown in Table 3, the NaHCO₃ (B) showed a significant effect with *p*-value of 0.025. The interaction of NaNO₃ and NaHCO₃ (AB) and NaNO₃ and BFCE (AC) and the quadratic terms of NaHCO₃ (B²), also significantly affected the protein yield with *p*-value of 0.047, 0.04 and 0.0203, respectively.

The interactive effect of variables on protein content was revealed by response surface plots (Fig. 16). It can be noted that an increase in protein content was obtained at NaNO₃ 2.5 g/L and NaHCO₃ from 2.1 to 6.3 g/L. The interaction between NaNO₃ and waste showed that the optimum NaNO₃ and waste range was 2.12–2.5 g/L and 35–75%, producing 50–60% protein. Moreover, an enhanced protein response was observed at

Table 2 Matrix and its corresponding responses for the CCD experiment

Run	Variables				Responses	
	NaNO ₃ (g/L)	NaHCO ₃ (g/L)	BFCE (%)	pH	Biomass dry weight (g/L)	Protein (%)
1	1.075	4.2	0.375	8.75	0.37	37.28
2	2.025	4.2	0.375	8.75	0.55	54.40
3	1.075	12.6	0.375	8.75	0.52	46.27
4	2.025	12.6	0.375	8.75	0.65	35.18
5	1.075	4.2	0.625	8.75	0.60	34.18
6	2.025	4.2	0.625	8.75	0.59	42.73
7	1.075	12.6	0.625	8.75	0.61	38.33
8	2.025	12.6	0.625	8.75	0.40	54.20
9	1.075	4.2	0.375	10.25	0.48	39.33
10	2.025	4.2	0.375	10.25	0.52	38.31
11	1.075	12.6	0.375	10.25	0.47	50.89
12	2.025	12.6	0.375	10.25	0.58	42.81
13	1.075	4.2	0.625	10.25	0.74	30.72
14	2.025	4.2	0.625	10.25	0.64	42.95
15	1.075	12.6	0.625	10.25	0.74	41.79
16	2.025	12.6	0.625	10.25	0.68	41.77
17	0.6	8.4	0.5	9.5	0.61	46.82
18	2.5	8.4	0.5	9.5	0.62	46.16
19	1.55	0.0	0.5	9.5	0.56	31.14
20	1.55	16.8	0.5	9.5	0.74	43.58
21	1.55	8.4	0.25	9.5	0.59	50.42
22	1.55	8.4	0.75	9.5	0.69	44.94
23	1.55	8.4	0.5	8	0.63	44.94
24	1.55	8.4	0.5	11	0.74	35.74
25	1.55	8.4	0.5	9.5	0.58	45.04
26	1.55	8.4	0.5	9.5	0.57	42.34
27	1.55	8.4	0.5	9.5	0.51	44.07
28	1.55	8.4	0.5	9.5	0.55	41.89
29	1.55	8.4	0.5	9.5	0.52	45.32
30	1.55	8.4	0.5	9.5	0.54	47.80
31	1.55	8.4	0.5	9.5	0.54	43.28
Control	2.5	16.8	0	9	0.60	55.11

the interaction between NaNO₃ and pH, with optimum ranges of 2.4–2.5 g/L and 8–8.9, respectively.

This result is in agreement with Colla et al. [49], they stated that the lower sodium nitrate concentrations (0.625 and 1.250 g/L) gave lower values for cellular proteins, while the highest levels of protein being obtained in Zarrouk's medium containing 1.875 or 2.500 g/L sodium nitrate.

Regarding the interaction between NaHCO₃ and waste, the optimum NaHCO₃ and waste ranges for maximum protein production were 4–12.6 g/L and 60–75%, respectively. Additionally, in the interactions between NaHCO₃ and pH, the optimum NaHCO₃ and pH ranges were

1.05–8.4 g/L and 8–9.5, respectively. Ultimately, the protein response was enhanced by the interaction between waste and pH, with optimum ranges of 67–75% and pH 8–8.9.

During the optimization process, the statistical tool produced 31 trials with several combinations of all independent variables. The predicated combination of independent variables showing the highest desirability value was selected as the predicted optimization value. The best biomass yield (0.8 g/L) and protein (54.15%) were with the following level of independent variables: NaNO₃ (2.5 g/L), NaHCO₃ (0.678 g/L), BFCE (33.08%) and pH=8.

Table 3 ANOVA table for response surface quadratic model for biomass yield and protein concentration

Variable	Response		Biomass dry weight (g/L)									
	Sum of squares	df	Mean square	F value	p-value	Sum of squares	df	Mean square	F value	p-value		
Model	765.07	14	54.65	2.50	0.0406 ^a	0.1675	10	0.1675	3.57	0.0074 ^a	Significant	
A-NaNO ₃	43.31	1	43.31	1.98	0.1780	0.0004	1	0.0004	0.088	0.768		
B-NaHCO ₃	131.70	1	131.70	6.03	0.0258 ^a	0.0113	1	0.0113	2.40	0.136		
C-BFCE	34.46	1	34.46	1.58	0.226	0.04	1	0.04	9.98	0.004 ^a	Significant	
D-pH	43.74	1	43.74	2.00	0.176	0.0258	1	0.0258	5.40	0.030 ^a	Significant	
A2	0.0312	1	0.0312	0.0014	0.970	0.000733	1	0.000733	0.16	0.69		
B2	144.70	1	144.70	6.63	0.0203 ^a	0.0053	1	0.0053	1.2	0.289		
C2	3.12	1	3.12	0.143	0.710	0.0036	1	0.0036	0.81	0.382		
D2	64.73	1	64.73	2.97	0.104	0.0149	1	0.0149	3.36	0.085		
A * B	101.00	1	101.00	4.63	0.047 ^a	0.0012	1	0.0012	0.26	0.614		
A * C	98.51	1	98.51	4.51	0.049 ^a	0.0441	1	0.0441	9.40	0.0061		
A * D	46.72	1	46.72	2.14	0.162	0.0006	1	0.0006	0.13	0.718		
B * C	24.21	1	24.21	1.11	0.307	0.0121	1	0.0121	2.58	0.123		
B * D	26.42	1	26.42	1.21	0.287	0.0000	1	0.0000	0.005	0.942		
C * D	6.79	1	6.79	0.311	0.584	0.0256	1	0.0256	5.46	0.030 ^a	Significant	
Residual	349.15	16	21.82				20					
Lack of fit	277.05	10	27.70	2.31	0.1594		14		1.76	0.2500	Not significant	
Pure Error	72.11	6	12.02				6					
Core total	1114.22	30					30					
R2 = 70.59%			Adjusted R2 = 44.85%			R2 = 72.58%		Adjusted R2 = 48.58%				

^a Significant value




Fig. 15 Three-dimensional response surface plot showing the interaction between the tested variables for optimum dry biomass

The model was verified experimentally. The actual results were then compared with the predicted value of the models in Eqs. (1) and (2), and the obtained values are shown in Table 4.

Amino acids profile of *S. platensis*

The protein quality of *S. platensis* depends mainly on its amino acid content, especially essential amino acids [50]. The result concerning the amino acids profile of *S. platensis* cultivated in SZM and optimized medium are shown in Table 5. The result of essential amino acid in *S. platensis* protein exhibited; was mainly leucine (8.36%) followed by valine (5.71%), whilst the lowest percentage was noted for histidine (1.62%) in the optimized medium. Likewise, leucine (8.16%) and valine (5.4%) were the major essential amino acids in SZM. Fortunately, the total essential amino acid was higher in the optimized medium (38.73%) than in SZM (36.98%). The results for non-essential amino acids in *S. platensis* protein indicated that glutamic acid was the major amino acid up to 14.65% and 14.26% in optimized and SZM, respectively. In contrast, cysteine was the lowest content (0.31%). It is evident from the results that TEAA in *S. platensis* protein

from the optimized medium using BFCE was a promising source of leucine, valine, isoleucine, lysine, glutamic acid, aspartic acid, alanine and arginine compared to the SZM. These levels and profile of amino acids in *Spirulina* are similar to that reported by Bashir et al. [51]

Conclusion

Microalga *S. platensis* can adapt to high concentrations of BFCE up to 75% substitution of SZM. Furthermore, the biomass and protein content similar to that of SZM. In contrast, direct cultivation on higher concentrations of BFCE led to low protein content and biomass compared to the SZM. The CCD predicated the optimum variables of NaNO₃ (2.5 g/L), NaHCO₃ (0.6 g/L), BFCE (33%), and pH = 8 to maximize the biomass yield and protein content. The resulting biomass yield was 0.56 g/L, and protein content was up to 52.5%. Also, protein quality was determined by its total essential amino acids content, which was 38.73% in the optimized medium and 36.98% in SZM. Economically, the newly optimized medium significantly saves approximately 96% NaHCO₃ compared to SZM without affecting the protein content and biomass production, and




Fig. 16 Three-dimensional response surface plot showing the interaction between the tested variables for optimum protein content production

Table 4 The actual and predicted values of the growth variables for maximizing each response

Variables				Actual value		Predicated value	
NaNO ₃ (g/L)	NaHCO ₃ (g/L)	BFCE (%)	pH	Biomass (g/L)	Protein (%)	Biomass (g/L)	Protein (%)
2.5	0.678	0.3308	8	0.566	52.58	0.8	54.15

Table 5 The essential and non-essential amino acid of *S. platensis* protein in SZM and optimized medium

Essential amino acid	SZM (%)	Optimized (%)	Non-essential amino acid	SZM (%)	Optimized (%)
Threonine (THR)	4.18	4.99	Glutamic (GLU)	14.26	14.65
Valine (VAL)	5.4	5.71	Aspartic (ASP)	9.11	9.5
Isoleucine (ISO)	5.21	5.4	Glycine (GLY)	4.6	4.96
Leucine (LEU)	8.16	8.36	Alanine (ALA)	6.49	6.96
Phenylalanine (PHE)	4.65	4.93	Tyrosine (TYR)	1.67	2.67
Histidine (HIS)	1.78	1.62	Arginine (ARG)	5.93	6.16
Lysine (LYS)	4.48	4.57	Proline (PRO)	3.54	3.82
Methionine (MET)	3.12	3.15	Cystine (CYS)	0.31	1.67
TEAA	36.98	38.73	Serine (SER)	3.2	3.87

TEAA total essential amino acids, SZM standard Zarrouk medium

these results indicating that BFCE could be used as a promising feedstock for the cost-effective large-scale cultivation of *Spirulina* as a microbial cell factory for protein.

Materials and methods

Collection, preparation, and chemical composition of BFC aqueous extract

The BFC was collected from Dakahlia Sugar Factory, Dakahlia province, Egypt. A hundred grams of solid waste was transferred into a pre-weighed 2 L screw cap Schott Duran® bottle (w_1) containing 1 L distilled water, autoclaved at 121 °C, 1.5 atm for 20 min. After autoclaving, the bottle was left to settle down, and then the clear beet filter cake extract (BFCE) was separated under aseptic conditions. Complete characterization of BFCE ingredients, including nitrate, ammonium, and phosphorus, was carried out. To confirm the toxic pollutants' absence, the concentration of the minerals was detected using inductively coupled plasma mass spectrometry (ICP-MS) before *S. platensis* inoculation.

Cultivation of *S. platensis* on different concentrations of BFCE

The BFCE-supplemented cultures were prepared by adding different volumes of beet filter cake extract (BFCE) to the standard Zarrouk's medium (SZM) [52], while SZM only served as the control treatment. Two strategies were applied in this study as following.

Batch culture experiment

S. platensis was cultivated in SZM supplemented with BFCE. The constituents of SZM were eliminated stepwise and substituted with increasing percentage volume of BFCE (SZM, 25%, 50%, 75% and 100% BFCE). The experiment was conducted in a replicate for each treatment. All treatments proceeded with a total volume of 400 mL in a 500 mL Erlenmeyer flask, then inoculated with 10% (v/v) exponentially growing culture (O.D=0.8 at 680 nm). At the same time, the incubation temperature was 26 ± 2 °C, 50 $\mu\text{mol/s/m}^2$ illuminations, 16:8 h light: dark cycle, and continuous bubbling with sterile air flow for seven days.

Incremental waste acclimatization experiment

In this design, the culture was subjected to a gradual increment in the BFCE concentration for each run, while the control was only SZM. In the first run, *S. platensis* inoculum was inoculated in the SZM and the 25% BFCE. Then after one week, each flask in the experiment was equally divided into two fractions (200 mL each) and centrifuged at 6000 rpm for 10 min. The first fraction's pellet was used for further analysis after lyophilization. In contrast, the other fraction's pellet was used as an inoculum in the next run

at an increment BFCE medium ratio equal to 25% BFCE higher than the current concentration. At the same time, the control flasks followed the same steps but with the same SZM for the next run. As a result, a total of four runs with BFCE concentrations of 25, 50, 75 and 100% for 28 days was the whole duration of the experiment, while the control for each run was still the same SZM constituents.

Analytical methods

Growth parameters determination

For the photosynthetic performance assessment, chlorophyll fluorescence was measured daily in dark-adapted cultures of *S. platensis* grown in SZM and BFCE using a pulse amplitude modulation fluorometer (PAM) (Aqua-Pen AP 110-C). The maximum photochemical efficiency of photosystem II (Fv/Fm) was measured [53, 54]. The culture optical density was also measured daily using a spectrophotometer at a wavelength of 680 nm [55]. For dry weight estimation, the culture of *S. platensis* was harvested by centrifugation at 6000 rpm for 10 min and washed with distilled water to remove any salt remains. The pellet of the *S. platensis* was dried in a lyophilizer for 48 h at -50 °C and weighed [56].

Estimation of chlorophyll-a, b and carotenoids contents

The pigment fraction (chlorophyll-a, b and carotenoids) was extracted by a known volume of 80% acetone and then measured spectrophotometrically at wavelengths 664, 647, 630 and 452 nm, respectively. The pigment concentrations were calculated by Jeffrey St, et al. [57] equations.

Biochemical characteristic determination

Protein content was determined according to Lowry's method [58]. The protein estimation was carried out by cell lysis using bovine serum albumin (BSA) as a standard. Total carbohydrates were determined according to the phenol sulfuric acid method described by Dubois et al. [59], and the concentration of carbohydrates was calculated from the standard curve of glucose. Lipid concentration was estimated by the sulfo-phospho-vanillin method described by Byreddy et al. [60], and the lipid content was calculated using a standard curve of cholesterol.

Experimental design for optimization of the protein content and growth yield in the *S. platensis* using central composite design

Central composite design (CCD) is the most popular RSM design and was applied to determine the combined influence of two or more variables used in the experiment. Based on the results of the previous experiments, four independent variables, namely (nitrate concentration (g/L), sodium bicarbonate concentration (g/L), BFCE concentration (%), and pH value) and two dependent

Table 6 Code limit for variables used in the experiment design

Factor	Unit	Symbol	Levels				
			- 2	- 1	0	+ 1	+ 2
NaNO ₃	(g/L)	X1	0.6	1.075	1.55	2.025	2.5
NaHCO ₃	(g/L)	X2	0	4.2	8.4	12.6	16.8
BFCE	(%)	X3	0.25	0.375	0.5	0.625	0.75
pH	-	X4	8	8.75	9.5	10.25	11

variables, namely: biomass yield (g/L) and protein content (%), were chosen for designing the experiment by CCD in Minitab[®] software with five levels of variables for selected factors (- 2, - 1, 0, + 1, + 2) as shown in Table 6.

CCD design generated 31 runs with seven replicates of central points, in addition to the control flask containing only SZM. Each flask was inoculated with 40 mL of *S. platensis* inoculum and incubated under optimum culturing conditions. The photosynthetic activity and optical density at OD=680 nm were measured daily, and at the end of the experiment the biomass yield was determined by dry weight and protein content by Lowry's method [58].

The predicted optimum results were calculated according to the following equation [61].

$$Y = \beta_0 + \sum \beta_i X_i + \sum \beta_{ii} X_{ii} + \sum \beta_{ij} X_{ij} \quad (3)$$

where Y is the response, β_i is the regression coefficient for each factor, β_{ii} is the regression coefficient for square effects, and β_{ij} is the regression coefficient for interaction.

The data obtained were analyzed using analysis of variance (ANOVA) using Design Expert 8 software. Based on the analysis of results, validation experiment for CCD was carried out.

Amino acid profile

The amino acids content of *S. platensis* grown in SZM and optimized medium was determined at Regional Center for Food and Feed (RCFF), Egypt, by using AOAC Method No. 994.12E [62] using high performance amino acid analyzer (Biochrom 30 plus series of Amino Acid Analyzer System (Biochrom, Cambridge, UK).

Statistical analysis

The mean, and standard error were calculated from the triplicate experimentations. The one-way ANOVA was applied to identify the significant differences between treatments using Duncan's test at a significant level $p \leq 0.05$. Growth medium optimization was performed through CCD method using Minitab[®] software. CCD consisting of variables and responses were analyzed statistically and subjected to analysis of variance (ANOVA)

to evaluate "the fit of the model" and the R^2 (coefficient determination) value was calculated by the regression equations.

Abbreviations

ANOVA	Analysis of variance
AOAC	Association of Official Agricultural Chemists
BFC	Beet filter cake
BFCE	Beet filter cake extract
CCD	Central composite design
Fv/Fm	Maximum quantum yield
ICP-MS	Inductively coupled plasma mass spectrometry
PAM	Pulse amplitude modulation
RCFF	Regional Center for Food & Feed
RSM	Response surface methodology
SCP	Single-cell protein
SZM	Standard Zarrouk's media
TEAA	Total essential amino acids
β_i	Regression coefficient for each factor
β_{ii}	Regression coefficient for square effects
β_{ij}	Regression coefficient for interaction

Supplementary Information

The online version contains supplementary material available at <https://doi.org/10.1186/s12934-023-02146-7>.

Additional file 1: Table S1. Growth parameters (optical density and photosynthetic activity) of *S. platensis* cultivated under different concentrations of NaNO₃, NaHCO₃, BFCE and pH in Central Composite Design. **Fig. S1.** Growth of *S. platensis* cultivated in the SZM and different BFCE treatments. **Fig. S2.** Growth of *S. platensis* cultivated in the SZM and BFCE treatments for incremental waste acclimatization for 28 days. **Fig. S3.** Optimization of growth parameters using Central Composite Design (CCD) for eight days of incubation.

Acknowledgements

The authors are thankful to the Research Funding Unit, Mansoura University, Egypt, for funding this project No. MU-SCI-20-12. Also, a great appreciation for Miss. Amany Saad (Bacteriology Lab, Faculty of Science, Mansoura University) and Miss. Heba Saad (Genetic Engineering & Biotechnology Unit, Mansoura University) for their help and advice in the CCD design and data explanations. Furthermore, thanks to The Science, Technology & Innovation Funding Authority (STDF) and The Egyptian Knowledge Bank (EKB) for open access publication funding.

Author contributions

Conceptualization, SS, and EE. Main experimental work and data analysis, SS, and EE. Writing-original draft preparation, SS, and EE. Writing-review and editing SS, EE, MH, GS, and HE. Supervision, EE, MH, GS, and HE. All authors contributed to the article and approved the submitted version. All authors read and approved the final manuscript.

Funding

Open access funding provided by The Science, Technology & Innovation Funding Authority (STDF) in cooperation with The Egyptian Knowledge Bank (EKB). This paper's results is a part of research project funded by Research Funding Unit, Mansoura University, Egypt. No. MU-SCI-20-12. Open access funding provided by The Science, Technology & Innovation Funding Authority (STDF) in cooperation with The Egyptian Knowledge Bank (EKB).

Availability of data and materials

All data generated and analyzed during this study are included in this manuscript and in its Additional file.

Declarations

Ethics approval and consent to participate

All authors read and approved the final manuscript and related ethics.

Consent for publication

All authors consent to this manuscript for publication after revising this final form.

Competing interests

The authors declare that the research was conducted in the absence of any commercial or financial relationships that could be construed as a potential competing interest.

Author details

¹Botany Department, Faculty of Science, Mansoura University, Mansoura 35516, Egypt.

Received: 12 April 2023 Accepted: 10 July 2023

Published online: 24 July 2023

References

- Afshar PG, et al. Bleaching of vegetable oils using press mud obtained from sugar industry. *Eur J Exp Biol*. 2014;4:677–84.
- Khawairakpam M, et al. Bioconversion of filter mud using vermicomposting employing two exotic and one local earthworm species. *Bioresour Technol*. 2009;100:5846–52. <https://doi.org/10.1016/j.biortech.2009.06.038>.
- Martins GL, et al. Physicochemical and bacterial changes during composting of vegetable and animal-derived agro-industrial wastes. *Bioresour Technol*. 2023;376:128842. <https://doi.org/10.1016/j.biortech.2023.128842>.
- Nježić ZB, et al. Kinetics and optimization of biodiesel production from rapeseed oil over calcined waste filter cake from sugar beet processing plant. *Fuel*. 2023;334:126581. <https://doi.org/10.1016/j.fuel.2022.126581>.
- El-Tayeh N, et al. Effect of sandy soil amendment with filter mud cake on growth and some ecophysiological parameters of *Daucus carota* and *Beta vulgaris* plants. *Catrina Int J Environ Sci*. 2019;18:97–103. <https://doi.org/10.21608/cat.2019.28613>.
- Prado RdM, et al. Filter cake and vinasse as fertilizers contributing to conservation agriculture. *Appl Environ Soil Sci*. 2013;2013:1–8. <https://doi.org/10.1155/2013/581984>.
- Mühling M, et al. Variation in fatty acid composition of *Arthrospira* (*Spirulina*) strains. *J Appl Phycol*. 2005;17:137–46. <https://doi.org/10.1007/s10811-005-7213-9>.
- Holman B, et al. *Spirulina* as a livestock supplement and animal feed. *J Anim Physiol Anim Nutr*. 2013;97:615–23. <https://doi.org/10.1111/j.1439-0396.2012.01328.x>.
- Sanchez M, et al. *Spirulina* (*Arthrospira*): an edible microorganism: a review. *Univ Sci*. 2003;8:7–24.
- Pleonsil P, et al. Anti-oxidant activity of holo-and apo-c-phycoerythrin and their protective effects on human erythrocytes. *Int J Biol Macromol*. 2013;60:393–8. <https://doi.org/10.1016/j.ijbiomac.2013.06.016>.
- Moraes CC, et al. C-phycoerythrin extraction from *Spirulina platensis* wet biomass. *Braz J Chem Eng*. 2011;28:45–9. <https://doi.org/10.1590/S0104-66322011000100006>.
- Ahsan M, et al. A review on culture, production and use of *Spirulina* as food for humans and feeds for domestic animals. *FAO Fisheries and Aquaculture Circular* (FAO) 2008.
- Nasseri A, et al. Single cell protein: production and process. *Am J Food Technol*. 2011;6:103–16.
- Ukaegbu-Obi KM. Single cell protein: a resort to global protein challenge and waste management. *J Microbiol Microb Technol*. 2016;1:5.
- Richmond A, et al. *Handbook of microalgal culture: applied phyecology and biotechnology*. USA: Wiley; 2013. <https://doi.org/10.1002/9781118567166>.
- Misumi M, et al. Relationship between photochemical quenching and non-photochemical quenching in six species of cyanobacteria reveals species difference in redox state and species commonality in energy dissipation. *Plant Cell Physiol*. 2016;57:1510–7. <https://doi.org/10.1093/pcp/pcv185>.
- Ogawa T, et al. Estimation of photosynthesis in cyanobacteria by pulse-amplitude modulation chlorophyll fluorescence: problems and solutions. *Photosynth Res*. 2017;133:63–73. <https://doi.org/10.1007/s11120-017-0367-x>.
- Kepekçi RA, et al. Enhancement of phenolic compound production in *Spirulina platensis* by two-step batch mode cultivation. *J Appl Phycol*. 2012;24:897–905. <https://doi.org/10.1007/s10811-011-9710-3>.
- Vonshak A, et al. Production of *Spirulina* biomass: Effects of environmental factors and population density. *Biomass*. 1982;2:175–85. [https://doi.org/10.1016/0144-4565\(82\)90028-2](https://doi.org/10.1016/0144-4565(82)90028-2).
- Genty B, et al. The relationship between the quantum yield of photosynthetic electron transport and quenching of chlorophyll fluorescence. *Biochim Biophys Acta (BBA)*. 1989;990:87–92. [https://doi.org/10.1016/S0304-4165\(89\)80016-9](https://doi.org/10.1016/S0304-4165(89)80016-9).
- Mallick N, et al. Use of chlorophyll fluorescence in metal-stress research: a case study with the green microalga *Scenedesmus*. *Ecotoxicol Environ Saf*. 2003;55:64–9. [https://doi.org/10.1016/S0147-6513\(02\)00122-7](https://doi.org/10.1016/S0147-6513(02)00122-7).
- Vonshak A, et al. Light and oxygen stress in *Spirulina platensis* (cyanobacteria) grown outdoors in tubular reactors. *Physiol Plant*. 1996;97:175–9. <https://doi.org/10.1111/j.1399-3054.1996.tb00494.x>.
- Zhou T, et al. Characterization of additional zinc ions on the growth, biochemical composition and photosynthetic performance from *Spirulina platensis*. *Bioresour Technol*. 2018;269:285–91. <https://doi.org/10.1016/j.biortech.2018.08.131>.
- Lu W, et al. Cultivation of *Spirulina platensis* using raw piggery wastewater for nutrient bioremediation and biomass production: effect of ferrous sulfate supplementation. *Desalin Water Treat*. 2020;175:60–7. <https://doi.org/10.5004/dwt.2020.24830>.
- Uslu L, et al. The effects of nitrogen deficiencies on the lipid and protein contents of *Spirulina platensis*. *Afr J Biotech*. 2011;10:386–9.
- Kong W-B, et al. Effect of glycerol and glucose on the enhancement of biomass, lipid and soluble carbohydrate production by *Chlorella vulgaris* in mixotrophic culture. *Food Technol Biotechnol*. 2013;51:62.
- Hayward J. Studies on the growth of *Phaeodaetylum tricornutum*. *Physiol Plant*. 1968;21:100–8. <https://doi.org/10.1111/j.1399-3054.1968.tb07234.x>.
- Bouarab L, et al. Heterotrophic and mixotrophic growth of *Micractinium pusillum* Fresenius in the presence of acetate and glucose: effect of light and acetate gradient concentration. *Water Res*. 2004;38:2706–12. <https://doi.org/10.1016/j.watres.2004.03.021>.
- Hachicha R, et al. Chapter 12—Nonconventional treatments of agro-industrial wastes and wastewaters by heterotrophic/mixotrophic cultivations of microalgae and Cyanobacteria. In: Bandh SA, Malla FA, editors., et al. *Valorization of Microalgal Biomass and Wastewater Treatment*. Amsterdam: Elsevier; 2023. p. 239–60. <https://doi.org/10.1016/B978-0-323-91869-5.00002-8>.
- Chang Y, et al. Cultivation of *Spirulina platensis* for biomass production and nutrient removal from synthetic human urine. *Appl Energy*. 2013;102:427–31. <https://doi.org/10.1016/j.apenergy.2012.07.024>.
- Li X, et al. Effect of nitrogen limitation on biochemical composition and photosynthetic performance for fed-batch mixotrophic cultivation of

- microalga *Spirulina platensis*. *Bioresour Technol.* 2018;263:555–61. <https://doi.org/10.1016/j.biortech.2018.05.046>.
32. Franklin LA, et al. Two components of onset and recovery during photoinhibition of *Ulva rotundata*. *Planta.* 1992;186:399–408. <https://doi.org/10.1007/BF00195321>.
 33. Lu C, et al. Characterization of PSII photochemistry in salt-adapted cells of cyanobacterium *Spirulina platensis*. *New Phytol.* 1999;141:231–9. <https://doi.org/10.1046/j.1469-8137.1999.00340.x>.
 34. Liu X, et al. Effects of organic carbon sources on growth, photosynthesis, and respiration of *Phaeodactylum tricornutum*. *J Appl Phycol.* 2009;21:239–46. <https://doi.org/10.1007/s10811-008-9355-z>.
 35. Tang D, et al. Physiological and biochemical responses of *Scytonema javanicum* (cyanobacterium) to salt stress. *J Arid Environ.* 2007;71:312–22. <https://doi.org/10.1016/j.jaridenv.2007.05.004>.
 36. Chaiklahan R, et al. Cultivation of *Spirulina platensis* using pig wastewater in a semi-continuous process. *J Microbiol Biotechnol.* 2010;20:609–14. <https://doi.org/10.4014/jmb.0907.07026>.
 37. Jiang Y, et al. Photosynthetic performance, lipid production and biomass composition in response to nitrogen limitation in marine microalgae. *Plant Physiol Biochem.* 2012;54:70–7. <https://doi.org/10.1016/j.plaphy.2012.02.012>.
 38. Rodrigues MS, et al. Fed-batch cultivation of *Arthrospira (Spirulina) platensis*: potassium nitrate and ammonium chloride as simultaneous nitrogen sources. *Bioresour Technol.* 2010;101:4491–8. <https://doi.org/10.1016/j.biortech.2010.01.054>.
 39. de Oliveira R-Y, et al. Chlorophyll production from *Spirulina platensis*: cultivation with urea addition by fed-batch process. *Bioresour Technol.* 2004;92:133–41. <https://doi.org/10.1016/j.biortech.2003.09.002>.
 40. Ayala F, et al. Experiments on *Spirulina* culture on waste-effluent media and at the pilot plant. In: Twelfth International Seaweed Symposium. Berlin: Springer; 1987. p. 91–3. https://doi.org/10.1007/978-94-009-4057-4_12.
 41. Li T, et al. Morphology, growth, biochemical composition and photosynthetic performance of *Chlorella vulgaris* (Trebouxiophyceae) under low and high nitrogen supplies. *Algal Res.* 2016;16:481–91. <https://doi.org/10.1016/j.algal.2016.04.008>.
 42. Piorreck M, et al. Biomass production, total protein, chlorophylls, lipids and fatty acids of freshwater green and blue-green algae under different nitrogen regimes. *Phytochemistry.* 1984;23:207–16. [https://doi.org/10.1016/S0031-9422\(00\)80304-0](https://doi.org/10.1016/S0031-9422(00)80304-0).
 43. Wu JF, et al. Amino acid composition and microbial contamination of *Spirulina maxima*, a blue-green alga, grown on the effluent of different fermented animal wastes. *Bull Environ Contam Toxicol (United States).* 1981;27:151. <https://doi.org/10.1007/BF01611001>.
 44. Nur MMA, et al. Enhancement of phycocyanin and carbohydrate production from *Spirulina platensis* growing on tofu wastewater by employing mixotrophic cultivation condition. *Biocatal Agric Biotechnol.* 2023;47:102600. <https://doi.org/10.1016/j.bcab.2023.102600>.
 45. Seyhaneyildiz Can S, et al. Effect of temperature and nitrogen concentration on the growth and lipid content of *Spirulina platensis* and biodiesel production. *Aquacult Int.* 2017;25:1485–93. <https://doi.org/10.1007/s10499-017-0121-6>.
 46. Pelizer LH, et al. Influence of inoculum age and concentration in *Spirulina platensis* cultivation. *J Food Eng.* 2003;56:371–5. [https://doi.org/10.1016/S0260-8774\(02\)00209-1](https://doi.org/10.1016/S0260-8774(02)00209-1).
 47. Krstić JB, et al. Biodiesel production from rapeseed oil over calcined waste filter cake from sugar beet processing. *Process Saf Environ Prot.* 2022;168:463–73. <https://doi.org/10.1016/j.psep.2022.10.021>.
 48. Raoof B, et al. Formulation of a low-cost medium for mass production of *Spirulina*. *Biomass Bioenergy.* 2006;30:537–42. <https://doi.org/10.1016/j.biombioe.2005.09.006>.
 49. Colla LM, et al. Production of biomass and nutraceutical compounds by *Spirulina platensis* under different temperature and nitrogen regimes. *Bioresour Technol.* 2007;98:1489–93. <https://doi.org/10.1016/j.biortech.2005.09.030>.
 50. Becker EW. Micro-algae as a source of protein. *Biotechnol Adv.* 2007;25:207–10. <https://doi.org/10.1016/j.biotechadv.2006.11.002>.
 51. Bashir S, et al. Functional properties and amino acid profile of *Spirulina platensis* protein isolates. *Biol Sci PJSIR.* 2016;59:12–9. <https://doi.org/10.52763/PJSIR.BIOL.SCI.59.1.2016.12.19>.
 52. Zarrouk C. Contribution a l'etude d'une Cyanophyceae. Influence de Divers Facteurs Physiques et Chimiques sur la croissance et la photosynthese de *Spirulina mixima*. Thesis University of Paris, France 1966.
 53. Cosgrove J, et al. Chlorophyll fluorescence terminology: an introduction. In: Chlorophyll fluorescence in aquatic sciences: methods and applications. Berlin: Springer; 2010. p. 1–17. https://doi.org/10.1007/978-90-481-9268-7_1.
 54. Markou G, et al. Cultivation of filamentous cyanobacteria (blue-green algae) in agro-industrial wastes and wastewaters: a review. *Appl Energy.* 2011;88:3389–401. <https://doi.org/10.1016/j.apenergy.2010.12.042>.
 55. Yap P, et al. Determination of biomass in *Spirulina* cultures by photopette. *Life Sci.* 2018;50:1–3.
 56. Vonshak A. *Spirulina platensis Arthrospira*: physiology, cell-biology and biotechnology. USA: CRC Press; 1997. <https://doi.org/10.1201/9781482272970>.
 57. St J, et al. New spectrophotometric equations for determining chlorophylls a, b, c1 and c2 in higher plants, algae and natural phytoplankton. *Biochem Physiol Pflanz.* 1975;167:191–4. [https://doi.org/10.1016/s0015-3796\(17\)30778-3](https://doi.org/10.1016/s0015-3796(17)30778-3).
 58. Lowry OH. Protein measurement with the Folin phenol reagent. *J Biol Chem.* 1951;193:265–75. [https://doi.org/10.1016/S0021-9258\(19\)52451-6](https://doi.org/10.1016/S0021-9258(19)52451-6).
 59. Dubois M, et al. Colorimetric method for determination of sugars and related substances. *Anal Chem.* 1956;28:350–6. <https://doi.org/10.1021/ac60111a017>.
 60. Byreddy AR, et al. A quick colorimetric method for total lipid quantification in microalgae. *J Microbiol Methods.* 2016;125:28–32. <https://doi.org/10.1016/j.mimet.2016.04.002>.
 61. Ahmad S, et al. Optimization of nutrient stress using *C. pyrenoidosa* for lipid and biodiesel production in integration with remediation in dairy industry wastewater using response surface methodology. *3 Biotech.* 2018;8:326. <https://doi.org/10.1007/s13205-018-1342-8>.
 62. AOAC. AOAC official method 994.12: amino acids in feeds. 18th edition: Association of Analytical Communities International Gaithersburg; 2010: 9–19.

Publisher's Note

Springer Nature remains neutral with regard to jurisdictional claims in published maps and institutional affiliations.

Ready to submit your research? Choose BMC and benefit from:

- fast, convenient online submission
- thorough peer review by experienced researchers in your field
- rapid publication on acceptance
- support for research data, including large and complex data types
- gold Open Access which fosters wider collaboration and increased citations
- maximum visibility for your research: over 100M website views per year

At BMC, research is always in progress.

Learn more biomedcentral.com/submissions

